

← CVP CSD Assessment Report 030907.pdf



As proposed, the Project will include fire hydrants and valves installed at approximately 500-1000 intervals. Pipe material will be plastic PVC. Blow-offs will be installed at all dead ends. Service lines and meter boxes will be installed per District standards. The water system in the Project area will operate under a static pressure of approximately 100 to 150 pounds per square inch.

Although most of the Project will be installed within the rights-of-way of public and private roads, a section of pipeline necessary to connect Sunshine Meadow Lane and Campbell Drive will have to be installed along the boundary lines of private property. The Gayle/Sunshine Meadow Home Owners Group, which is the Project proponent, has advised the District that the affected landowners are willing to grant the easements necessary for construction and operation of the portion of pipeline crossing private property. The District will require that the affected property owners grant such easements as a condition of receiving District water service.

